



SHURFLO® LVPO F4 LOW VOLUME FILTER

DELIVER QUALITY DRINKING WATER FOR ICE AND COFFEE APPLICATIONS

LVPO-F4 Cartridge: 94-470-02



APPLICATIONS

Ice
Coffee
Espresso

FEATURES • BENEFITS

Designed for versatile installation capabilities
Optional water boost to ensure consistent flow and pressure
Scale and particulate reduction
NSF® Standard 42

INSTALLATION TIPS

Do not use with water that is microbiologically unsafe or of unknown quality without adequate disinfection before or after this system

Filter must be protected against freezing, which can cause cracking of the filter and water leakage

Install this filter on cold water lines only. Do not use on water lines exceeding 100°F (37.2°C). Minimum water pressure of 20 psi (1.4 bar) and a maximum water pressure of 125 psi (8.62 bar) is required

When installing behind an appliance use ample amount of tubing to allow removal of the appliance to prevent damage to the tubing, filter or fittings. Damage to tubing, filter or fittings could cause leakage and damage

OPERATION TIPS

Change cartridge when capacity is reached or at least once a year

Change cartridge if taste and odor return

Always flush filter at time of installation and cartridge change

SIZING


Service Flow Rate: 0.5. gpm (1.9 Lpm)

Treatment Capacity: 2,200 grains or 250 gallons (946 L)

Ports: 3/8" NPT

SHURFLO® LVPO F4 LOW VOLUME FILTER

94-470-02



SPECIFICATIONS

Overall Dimensions

16.1" L x 3.3" dia (40.89 x 8.38 cm)

Ports

3/8" NPT

Service Flow Rate

0.5 gpm (1.9 Lpm)

Rated Capacity

2,200 Grains Service Life or 250 gallons
(946 L @ 150 ppm)

Pressure Requirements

20-125 psi (1.4-8.2 bar)

Temperature

40-100°F (4.4-37.8°C)

WARRANTY

Limited Pentair® Warranty is valid from the date of manufacture or with proof of purchase:

2088 - One year
Water Boost - One year
Water Pressure Reducer Valve - One year
8000, 8025, 8010, 8075, 8095 - One year

Pentair will provide a copy of the warranty upon request.



FILTRATION & PROCESSING SOLUTIONS

EVERPURE-SHURFLO WORLD HEADQUARTERS, 1040 MUIRFIELD DRIVE, HANOVER PARK, IL 60133 USA • WWW.EVERPURE.COM
800.942.1153 MAIN (US ONLY) • 630.307.3000 MAIN • 630.307.3030 FAX • CSEVERPURE@PENTAIR.COM EMAIL

EVERPURE-SHURFLO AUSTRALIA / NEW ZEALAND, 1-21 MONASH DRIVE, DANDENONG SOUTH, VIC, 3175, AUSTRALIA
1300.576.190 TEL • AU.EVERPURE@PENTAIR.COM EMAIL

EVERPURE-SHURFLO CHINA, 21F CLOUD 9 PLAZA, NO 1118, SHANGHAI, 200052, CHINA
86.21.3211.4588 TEL • 86.21.3211.4580 FAX • CHINA.WATER@PENTAIR.COM EMAIL

EVERPURE-SHURFLO INDIA, GREEN BOULEVARD, B-9/A, 7TH FLOOR - TOWER B SECTOR 62, NOIDA - 201301
91.120.419.9444 TEL • 91.120.419.9400 FAX • INDIACUSTOMER@PENTAIR.COM EMAIL

EVERPURE-SHURFLO EUROPE, PENTAIR WATER BELGIUM BVBA, INDUSTRIEPARK WOLFSTEE, TOEKOMSTLAAN, 30 B-2200 HERENTALS, BELGIUM
+32.(0).14.283.500 TEL • +32.(0).14.283.505 FAX • SALES@EVERPURE-EUROPE.COM EMAIL

EVERPURE-SHURFLO JAPAN INC., HASHIMOTO MN BLDG. 7F, 3-25-1 HASHIMOTO, MIDORI-KU, SAGAMIHARA-SHI KANAGAWA 252-0143, JAPAN
81.(0)42.775.3011 TEL • 81.(0)42.775.3015 FAX • INFO@EVERPURE.CO.JP EMAIL

EVERPURE-SHURFLO SOUTHEAST ASIA, 390 HAVELOCK ROAD, #04-01, KING'S CENTRE, SINGAPORE 169662
65.6795.2213 TEL • FAX: 65.6795.2219 FAX • CSEVERPURE@PENTAIR.COM EMAIL

All Pentair trademarks and logos are owned by Pentair, Inc. All other brand or product names are trademarks or registered marks of their respective owners. Because we are continuously improving our products and services, Pentair reserves the right to change specifications without prior notice. Pentair is an equal opportunity employer.